



ENERGY INCIDENT REGISTER

Independent public record · energyincidentregister.com

PLANNING EVIDENCE PACK

North Falls Offshore Wind Farm

Incidents on record and planning decisions nearby, for a 1,000 MW offshore wind site

PLANNING AUTHORITY

The Planning Inspectorate - National Infrastructure

LOCATION

22km Offshore, Lowestoft, The Planning Inspectorate - National Infrastructure, United Kingdom

PACK REFERENCE

EIR-PACK-D-NORTH-FALLS-OFFSHORE-WIND-FARM-GB-10913

DATA AS OF

29 October 2026

REVIEW STATUS

Made automatically for a decided application, free to read. Not desk-reviewed.

Made from the register on 29 October 2026, when it was opened. Free to read: this application was decided (granted, 14 May 2026). Made today from the register as it stands now; it is not the evidence that was before the decision.

Information only. Not engineering, fire safety or legal advice.



Contents

	At a glance	3
	The site on a map	4
	The site and the UK record	5
1	Key findings for this site	6
2	Incidents in the UK (12)	6
3	Planning decisions on offshore wind schemes nearby	7
4	Every recorded incident within 50 km	7
5	Grid-scale incidents at sites of a similar size	8
6	Lessons for a grid-scale site	9
7	Worldwide context	11
8	Kept apart: other battery entries in the UK (0)	12
9	Using this pack	12
10	How this pack was made and checked	13

Every figure in this pack comes from the register or the government planning database as they stood on 29 October 2026. Each numbered section names its sources, and every incident links to its entry page, which lists all sources.

At a glance

North Falls Offshore Wind Farm

OFFSHORE WIND INCIDENTS IN THE UK

12

4 classed as major
Section 2

NEAREST UK INCIDENT

14 km

EIR-0447, Great Yarmouth, Norfolk
Section 2

SCHEMES REFUSED WITHIN 40 KM

0

final outcome refused, of 0 sites with a refusal, withdrawal or appeal
Section 3

GRID-SCALE INCIDENTS AT SITES OF 500 TO 2,000 MW

9

worldwide
Section 5


What the data shows

- 1 The register holds 12 incidents at grid-scale offshore wind sites in the UK, 4 of them major. 1 recorded incident lies within 50 km of the site. The nearest, EIR-0447, is about 14 km away.
- 2 No offshore wind site within 40 km has had an application refused, withdrawn or taken to appeal in the government planning database.
- 3 Worldwide the register holds 40 incidents at grid-scale offshore wind sites in 10 countries; 6 involved fire or overheating. These are counts of published reports, not rates.

Counts are of incidents in the register, which is built from published reporting. They are not rates and not a complete census. Review: Made automatically for a decided application, free to read. Not desk-reviewed.

The site on a map

The site point, with every scheme within 40 km where an application was refused, withdrawn or taken to appeal (section 3), and every incident in the register within the frame. Numbers follow distance from the site. Schemes under 1 MW are not shown.



- Site
- Refused
- Granted on appeal
- Granted
- Withdrawn
- Pending or undecided
- Incident
- Built-up area
- Major road

Base map made with Natural Earth (naturalearthdata.com, public domain). Scheme points: Renewable Energy Planning Database, Department for Energy Security and Net Zero (Open Government Licence v3.0). Incident points: Energy Incident Register, mapped to a town or a site, never an address. Straight-line distances.

The site and the UK record

Each grid-scale battery incident in the UK that has a map point, against the site. Section 2 gives each one in full, with a note against the NFCC guidance.



Base map made with Natural Earth (public domain). The blue box is the area of the previous map.

UK grid-scale incidents

- EIR-0447 · 14 km · 2023**
Fire destroyed turbine at Scroby Sands Offshore Wind Farm in 2023
- EIR-0029 · 345 km · 2024**
Second blade failure of 2024 at Dogger Bank A offshore wind farm
- EIR-0758 · 345 km · 2024**
Service vessel collision damages turbine at Orsted's Hornsea Project One offshore wind farm (provisional)
- EIR-1778 · 345 km · 2018**
Engineer loses arm during repair at North Sea Siemens Gamesa turbine (provisional)
- EIR-0431 · 2025**
Fire-damaged offshore turbine reported under removal, United Kingdom (provisional)
- EIR-0028 · 2024**
Blade damage during construction at Dogger Bank A offshore wind farm
- EIR-1662 · 2024**
Technician falls from gangway at Dogger Bank Wind Farm (provisional)
- EIR-2614 · 2023**
Offshore wind turbine catches fire at North Denes Beach, Lowestoft, Suffolk
- EIR-1781 · 2023**
Engineer reported to have lost an arm on a North Sea wind farm (provisional)
- EIR-1752 · 2023**
Blade section detaches at Humber Gateway off Holderness (provisional)
- EIR-0900 · 2021**
Turbine components fall into sea at Ormonde offshore wind farm, Irish Sea
- EIR-0962 · 2020**
Five workers injured in installation vessel accident at Triton Knoll wind farm

● Major ● Significant ● Minor

1 Key findings for this site

- The register holds **12** offshore wind incidents in the UK.
- The nearest is [EIR-0447](#), Fire destroyed turbine at Scroby Sands Offshore Wind Farm in 2023, about 14 km from the site.
- 1 recorded incident of any size lie within 50 km of the site (1 at grid-scale sites).
- No offshore wind site within 40 km has had an application refused, withdrawn or taken to appeal, in the government planning database.
- 9 grid-scale incidents worldwide happened at sites between 500 and 2,000 MW.

Counts are of incidents in the register, which is built from published reporting. They are not rates and not a complete census.

2 Incidents in the UK (12)

Nearest to the site first. Distance is a straight line from the site point to the place the entry is mapped to (a town or a site).

REFEREN CE	YEAR	INCIDENT	FROM THE SITE	SEVERITY	MW
EIR-0447	2023	Fire destroyed turbine at Scroby Sands Offshore Wind Farm in 2023	14 km	Major	
EIR-0029	2024	Second blade failure of 2024 at Dogger Bank A offshore wind farm	345 km	Significant	1,200
EIR-0758	2024	Service vessel collision damages turbine at Orsted's Hornsea Project One offshore wind farm [provisional]	345 km	Significant	
EIR-1778	2018	Engineer loses arm during repair at North Sea Siemens Gamesa turbine [provisional]	345 km	Major	
EIR-0431	2025	Fire-damaged offshore turbine reported under removal, United Kingdom [provisional]	not mapped	Significant	
EIR-0028	2024	Blade damage during construction at Dogger Bank A offshore wind farm	not mapped	Significant	1,200
EIR-1662	2024	Technician falls from gangway at Dogger Bank Wind Farm [provisional]	not mapped	Major	
EIR-2614	2023	Offshore wind turbine catches fire at North Denes Beach, Lowestoft, Suffolk	not mapped	Significant	
EIR-1781	2023	Engineer reported to have lost an arm on a North Sea wind farm [provisional]	not mapped	Major	
EIR-1752	2023	Blade section detaches at Humber Gateway off Holderness [provisional]	not mapped	Minor	219
EIR-0900	2021	Turbine components fall into sea at Ormonde offshore wind farm, Irish Sea	not mapped	Significant	150
EIR-0962	2020	Five workers injured in installation vessel accident at Triton Knoll wind farm	not mapped	Significant	857

3 Planning decisions on offshore wind schemes nearby

Sites within 40 km of the site where an application was refused, withdrawn or taken to appeal, from the government's Renewable Energy Planning Database, those in The Planning Inspectorate - National Infrastructure first. Each row is one site: a refused scheme that was sent in again is one row, with every application listed. The final outcome is that of the latest application. Schemes under 1 MW are listed apart, below the table. Councils with a scheme in this radius: none. The database does not record the reasons for a decision; the council's planning record does, under the application number.

None in the database within 40 km.

All offshore wind applications within 40 km by database status: Operational 1, Awaiting Construction 1. A "council record" mark means the council's own planning record shows a decision the government database did not yet have; the site page explains it. A "newer official status" mark means an official source (a council record or committee minutes, the Scottish Government or the Planning Inspectorate) shows a newer status than the government database; the outcome uses it, and the row names the source and the day it was checked.

4 Every recorded incident within 50 km

Measured on a map from the place name Lowestoft, Suffolk (Ordnance Survey open place names). Every size of site is included here, so a home battery fire nearby is shown, marked as such. Entries are found by their map point only, never by matching words in the text. 8 UK entries have no map point yet and cannot be measured.

REFEREN CE	YEAR	INCIDENT	FROM THE SITE	KIND OF SITE
EIR-0447	2023	Fire destroyed turbine at Scroby Sands Offshore Wind Farm in 2023	14 km	Grid-scale site

5 Grid-scale incidents at sites of a similar size

Sites between 500 and 2,000 MW, worldwide, newest first. Capacity is the site's, where the reporting gives it.

REFERENCE	YEAR	INCIDENT	COUNTRY	SEVERITY	MW
EIR-0167	2026	Fire takes single turbine out of service at Greater Changhua 4 wind farm	Taiwan	Significant	920
EIR-0730	2026	Blade failure on Vestas 15MW turbine at He Dreiht offshore wind farm	Germany	Significant	960
EIR-0256	2026	Vessel collision at Port of Esbjerg damages nine wind turbine blades [provisional]	Denmark	Significant	1,100
EIR-1112	2025	Lightning strike damages already faulty blade at Vineyard Wind offshore turbine	United States	Minor	800
EIR-0029	2024	Second blade failure of 2024 at Dogger Bank A offshore wind farm	United Kingdom	Significant	1,200
EIR-0027	2024	Blade failure at Vineyard Wind 1 offshore wind project, Massachusetts	United States	Major	806
EIR-0028	2024	Blade damage during construction at Dogger Bank A offshore wind farm	United Kingdom	Significant	1,200
EIR-0797	2022	Drifting bulk carrier damages foundation at Hollandse Kust Zuid wind farm [provisional]	Netherlands	Significant	1,500
EIR-0962	2020	Five workers injured in installation vessel accident at Triton Knoll wind farm	United Kingdom	Significant	857

6 Lessons for a grid-scale site

The lessons written into the register's entries: every UK grid-scale incident first, then major grid-scale incidents elsewhere. No home battery lessons. Each is the register's reading of the published reporting, not a finding by an investigator.


1. Motion-compensated gangways should give a clear audible and visual warning before automatic retraction, or be taken out of service until they can. [EIR-1662](#)
2. Personnel transfers at height need clear supervision, communication and a workable manual override. [EIR-1662](#)
3. Operators should review gangway arrangements after safety notices on these systems. [EIR-1662](#)
4. A nacelle fire at an offshore wind turbine can result in total loss of the unit given the difficulty of firefighting access at sea. [EIR-0447](#)
5. Decommissioning a fire-damaged offshore turbine can require extensive licensing processes with regulators such as marine management authorities, extending timelines well beyond the incident itself. [EIR-0447](#)
6. Serious injury reports should record the site, date, task and equipment so other operators can learn from them. [EIR-1781](#)
7. Work on offshore turbines should be controlled so people cannot be injured by moving parts. [EIR-1781](#)
8. A reported court finding of duty breaches is a prompt to review how contractor work is planned and supervised, without treating the short report as a full account. [EIR-1781](#)
9. Isolation should be verified before work starts on a turbine blade, not assumed from an earlier check. [EIR-1778](#)
10. Maintenance procedures should require a further check that power is off before a repair begins. [EIR-1778](#)
11. After a serious maintenance injury, equipment and procedures should be reviewed promptly. [EIR-1778](#)
12. An offshore turbine fire can lead to removal, so operators should include loss of a single unit in availability and revenue contingency planning. [EIR-0431](#)
13. Offshore turbine removal after fire needs heavy lift vessels and marine support, so pre-agreed contracts should be in place. [EIR-0431](#)
14. A nacelle fire on an offshore turbine requires plans that cover personnel accounting, exclusion zones and debris recovery at sea. [EIR-0431](#)
15. A blade on a turbine left with rotor locked and yaw disabled can fail in high winds, so operators should check weather exposure limits before locking during commissioning. [EIR-0029](#)
16. Separate root causes for similar blade failures on one design require operators to review each incident on its own merits rather than assume a single fix. [EIR-0029](#)
17. An offshore installation error can damage a blade on an installed turbine, so operators should apply the same quality controls and hold points to marine lifts as to factory work. [EIR-0028](#)
18. Early findings that limit the issue to one blade still require checks on other units installed in the same campaign or by the same crew. [EIR-0028](#)
19. A marine area restriction after blade damage allows safe resumption only once findings confirm the cause is confined to the affected unit. [EIR-0028](#)
20. Collision by a service operation vessel damaged a turbine, so operators should review approach procedures and exclusion zones around offshore turbines. [EIR-0758](#)

21. Vessel contact with a turbine caused damage, so operators should require structural inspection of the tower and foundation before return to service. [EIR-0758](#)
22. Service vessel collision at an offshore wind farm carries risk of damage, so insurers should check crew training records for close-quarters manoeuvring. [EIR-0758](#)
23. Where an offshore turbine fire is detected remotely, operators should have a documented response that includes notifying the coastguard and confirming the status of the incident to the public. [EIR-2614](#)
24. Operators should record when a fault is detected, when vessels are dispatched and when the fire is confirmed out, so that public questions can be answered quickly. [EIR-2614](#)
25. Where visible smoke is reported by the public, operators and authorities should issue a short factual statement early to prevent speculation about spread or casualties. [EIR-2614](#)
26. Major component exchange on offshore turbines needs rigorous lifting equipment checks and procedures, as a dropped hub and blades can fall into the sea. [EIR-0900](#)
27. Operators must hold environmental contingency plans for offshore maintenance, ready for debris in the sea or on shorelines. [EIR-0900](#)
28. Prompt authority alerts after offshore incidents limit environmental and reputational harm. [EIR-0900](#)
29. An installation vessel at night needs tested plans for multiple casualties and helicopter evacuation from a working deck. [EIR-0962](#)
30. A multi-casualty event on an installation vessel should trigger an immediate return to port to preserve evidence. [EIR-0962](#)
31. Vessel operator, project operator and regulator should agree investigation duties before mobilisation. [EIR-0962](#)
32. Issue a notice to mariners promptly when a blade section from an offshore turbine enters the sea and remains unaccounted for. [EIR-1752](#)
33. Keep the affected turbine shut down and continue to monitor the site while debris may still be adrift or submerged. [EIR-1752](#)
34. Plan component and vessel availability for blade replacement while the cause is still being investigated. [EIR-1752](#)
35. Vessel captains must maintain a proper lookout when navigating near offshore wind turbines. [EIR-0498](#)
36. Offshore wind farms in fishing areas need clear marking and communication to local fleets. [EIR-0498](#)
37. A 107 metre blade with a manufacturing bond defect can shed large fragments into the sea, so operators must plan for marine and shoreline debris recovery. [EIR-0027](#)
38. Radiographic inspection of all blades from one factory is needed when a production deviation is found, to catch defects missed by earlier quality checks. [EIR-0027](#)
39. A blade fault traced to one factory requires clear traceability records so the affected population can be identified quickly. [EIR-0027](#)
40. A blade failure in commissioning can spread debris over a wide marine area, so plans must cover extended sea and beach recovery with pre-agreed contractors. [EIR-0005](#)

7 Worldwide context

40 incidents at grid-scale offshore wind sites in 10 countries; 6 involved fire or overheating and 10 are classed as major.

Grid-scale incidents by year: worldwide and UK



Counts of grid-scale incidents in the register by the year they happened; 2 earlier entries are not shown. More recent years hold more entries partly because more is reported and found online. A rising count is not, by itself, a rising rate. The same figures are in the table below.

YEAR	WOR LDW IDE	UK
2026	5	0
2025	4	1
2024	7	4
2023	6	4
2022	4	0
2021	4	1
2020	5	1
2019	0	0
2018	3	1
2017	0	0
Earlier	2	

STAGE OF LIFE	INCI DEN TS	SHA RE
Commissioning	17	43%
Normal operation	13	33%
Maintenance	5	13%
Not stated	5	13%

More recent years hold more entries partly because more is reported and found online. A rising count is not, by itself, a rising rate.

8 Kept apart: other battery entries in the UK (0)

Home, farm and business batteries, concerns raised where nothing failed, and events at battery sites that were not battery failures. NFCC's grid-scale guidance does not cover home batteries ("Domestic BESS are outside the scope of this guidance."), so they are listed here and not in the tables above.

None.

9 Using this pack

Paragraphs you can paste into a planning statement or a consultee response. They are neutral, use only figures from this pack, and each carries its citation. Please keep the citation with the text.

Incidents in the UK

The Energy Incident Register, a public record built from published reporting, lists 12 incidents at grid-scale offshore wind sites in the UK as of 29 October 2026, 4 of them classed as major. The nearest to the site is EIR-0447 (Fire destroyed turbine at Scroby Sands Offshore Wind Farm in 2023), about 14 km away in a straight line.

Source: Energy Incident Register, planning evidence pack EIR-PACK-D-NORTH-FALLS-OFFSHORE-WIND-FARM-GB-10913, section 2, data as of 29 October 2026. Entry EIR-0447: <https://energyincidentregister.com/incident/eir-0447/>

Worldwide context

Worldwide, the Energy Incident Register lists 40 incidents at grid-scale offshore wind sites in 10 countries as of 29 October 2026. Of these, 6 involved fire or overheating and 10 are classed as major. The register counts published reports of incidents; the figures are not failure rates.

Source: Energy Incident Register, planning evidence pack EIR-PACK-D-NORTH-FALLS-OFFSHORE-WIND-FARM-GB-10913, section 7, data as of 29 October 2026.

Sites of a similar size

The register lists 9 grid-scale incidents worldwide at sites between 500 and 2,000 MW, where the reporting gives the capacity.

Source: Energy Incident Register, planning evidence pack EIR-PACK-D-NORTH-FALLS-OFFSHORE-WIND-FARM-GB-10913, section 5, data as of 29 October 2026.

10 How this pack was made and checked

1. The register is built from published reporting: news, fire service statements, regulators and court records. Each entry lists its sources on its own page. Entries marked provisional rest on thinner sourcing and are rechecked.
2. Grid-scale or not: an entry is grid-scale unless its reporting describes a home, farm or business battery, or an event that was not a battery failure. The rule is the same for every pack.
3. Distances are measured from the site point (the place name Lowestoft, Suffolk (Ordnance Survey open place names)) to each entry's map point, which is a town or a site, never an address.
4. Planning decisions come from the government's Renewable Energy Planning Database (Open Government Licence v3.0), with corrections where a council's own record shows a later decision.
5. **Desk review.** The EIR editorial desk checks each bought pack within 2 working days (Monday to Friday) of the order:
 - a. The site point and planning authority match the planning record, or the details the buyer gave.
 - b. Each UK incident is a separate event, not one fire written twice, and sits in the right table: grid-scale sites in the main table, home, farm and business batteries apart.
 - c. Each UK grid-scale incident has a note, and every quoted passage matches the NFCC text at the link given.
 - d. The three nearest planning decisions match the council's own planning record.
 - e. The distances to the nearest incidents look right on a map.
 - f. Nothing in the pack comes from a confidential submission or names a private person.
6. If anything needs changing, the desk makes a new version and emails the link. Every version is fixed and dated, and earlier versions stay available at the same link. The method is at energyincidentregister.com/pack-method.
7. Information only. It is not engineering, fire safety or legal advice. See [the disclaimer](#).

How to cite: Energy Incident Register, planning evidence pack EIR-PACK-D-NORTH-FALLS-OFFSHORE-WIND-FARM-GB-10913, data as of 29 October 2026, energyincidentregister.com.

A correction to any entry is free for anyone: [corrections](#). Questions about this pack: editor@energyincidentregister.com.